

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 10 T 48N R 31W	5
	S 10 T 48N R 31W	6
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

I, Stephan J. Szyszkoski, in a field survey on 6 05/04/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(5-Sec. 10) North 1/16 corner, Section 10. Not established in the original survey.

(6-Sec. 10) Northeast 1/16 corner, Section 10. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(5-Sec. 10) Established the corner midway and on a straight line between Quarter corner 1304.36' north and Center of Section 1304.36' south. The position for the corner falls on a granite knob. The monument is a 1"IDx13" iron pipe with 4" alum. MDNR cap with a 5/8"x12" rebar grouted inside, which rebar is grouted into a 3/4"x4" deep hole drilled into the granite.

(6-Sec. 10) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(5) Set 1"ID capped pipe described in Part B.
 Set measuring nail with MDNR tag in the side of:
 4" Balsam N25E 4.9' mrkd "1/16S BT"
 6" Spruce S45E 15.25' do
 7" Spruce S28W 11.75' do
 5" Spruce N68W 19.4' do
 Bearings are magnetic.

(6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 6" twin Sugar N12W 12.15' mrkd "1/16S NBT"
 9" Sugar S61E 7.55' do
 9" Y.Birch S22E 13.35' do
 3" Sugar S73W 5.1' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 07/07/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division