

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 48 N. R. 32 W.	B-1
2. PROPERTY CONTROLLING IN SECTION 6	T. 48 N. R. 32 W.	1, 2
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 21, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner B-1: Original monument and accessories not found.

Corner 1: Not set on original survey nor subsequently apparently.

Corner 2: Not set on original survey nor subsequently apparently. Found old post S02°W 4.5'.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner B-1: Re-established on line between section corners east and west.

Corner 1: Established on line between corners east and west.

Corner 2: Established on line between corners east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner B-1: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.

5" Cedar N40°E 49.3' 1/4S, NBT
 7" Balsam S28°W 10.6' 1/4S, NBT
 5" Balsam S13°E 9.7' 1/4S, NBT

Corner 1: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.

8" Cedar S60°W 17.4' 1/16S, BT
 6" Balsam S12°E 3.6' 1/16S, BT
 7" Spruce N53°E 5.8' 1/16S, BT

Corner 2: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.

10" W. Pine N69°E 14.8' 1/16S, BT
 8" Cedar N78°W 40.8' 1/16S, BT
 7" W. Pine S66°W 28.4' 1/16S, BT
 10" Spruce squared N44°W 6.5'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett
CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett

DATE 11/3/77

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

