

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 48 N. R. 32 E. W.	L7, M6, & M7
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corners L7, M6, & M7:** Original posts or accessories not found.
- Corners L7 & M6:** No subsequent monuments found.
- Corner M7:** Found a 4"x4"x5' squared cedar post, 3-5 years old, in place, as set by unknown party.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner L7:** Re-established on 12/8/72 on line between section corners 39.979 ch. to E and to W.
- Corner M6:** Re-established on 10/12/71 proportionately on line between original section corner 39.770 ch. N and section corner 198.852 ch. S.
- Corner M7:** The found post checked perfectly for alignment and proportionate distance between section corners 79.541 ch. N and 159.082 ch. S; therefore accepted the post as marking the true corner and on 12/16/70 replaced the monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Monuments for all three corners:** 1" I.D. x 36" iron pipe with 4" aluminum cap.
- Witnesses for Corner L7:** Sugar Maple 13 N53°W (mag.) 15.0 ft. "1/4S, NBT"
W. Pine 12 S86°E (mag.) 27.4 ft. "1/4S, NBT"
 - Witnesses for Corner M6:** W. Pine 6 S53°W (mag.) 5.2 ft. "1/4S, NBT"
Y. Birch 5 N26°E (mag.) 21.0 ft. "1/4S, NBT"
R. Maple 8 N63°E (mag.) 11.9 ft. "1/4S, NBT"
 - Witnesses for Corner M7:** Sugar Maple 12 N41°E (mag.) 38.8 ft. "S18, NBT"
Sugar Maple 8 N89°W (mag.) 22.4 ft. "S24, NBT"
W. Birch 14 S61°E (mag.) 37.7 ft. "S19, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE March 2, 1973

APPROVED AND SIGNED BY Keith L. Sackett CHIEF OF SURVEY PARTY
Arthur O. Enger MICHIGAN REGISTERED LAND SURVEYOR DATE March 2, 1973

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581