

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 48 N. R. 32 <del>XX</del> W.	K 8
2. PROPERTY CONTROLLING IN SECTION 23	T. 48 N. R. 32 <del>XX</del> W.	14 & 16
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. W.	
4. LOT NO. . . . . , RECORDED PLAT . . . . .		
5. PRIVATE CLAIMS . . . . .		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, **Arthur O. Enger** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on **see below** 19 , established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19 , found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner K8:** Original post or accessories not found. Found a sq. balsam post of recent vintage N86°E 73.7 ft. from corner, for an approx. corner.

**Corner 14 & 16:** Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner K8:** Found no record, physical, or measurement evidence to support the found post; therefore on 5/6/71, re-established the corner on line between Sec. Corners 39.99 ch. to N and to S.

**Corner 14:** Established 5/6/71 on line between Sec. Cor. 19.995 ch. S and 1/4 cor. 19.995 ch. N.

**Corner 16:** Established 9/28/71 on line between Sec. Cor. 20.229 ch. E and 1/4 corner 20.229 ch. W.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Monuments for all three corners:** 1" I.D. x 36" iron pipe with 4" aluminum cap.

**Witnesses for Corner K8:** W. Birch 16 S65°E (mag.) 2.2 ft. "1/4S, NBT"  
R. Maple 9 N 4°W (mag.) 36.3 ft. "1/4S, NBT"

Also squared & scribed a 3" balsam N17°W 3.0 ft. from corner.

**Witnesses for Corner 14:** Sugar Maple 10 S25°E (mag.) 8.0 ft. "1/16S, BT"  
Sugar Maple 6 N55°E (mag.) 14.3 ft. "1/16S, BT"

**Witnesses for Corner 16:** Cedar 10 S 6°W (mag.) 9.7 ft. "1/16S, BT"  
Cedar 8 N56°W (mag.) 8.7 ft. "1/16S, BT"

Also squared & scribed a cedar 1 ft. west.

SIGNED BY

DATE

SURVEYOR'S MICHIGAN REGISTRATION NO.

LEGAL

FOR STATE AND UNITED STATES AGENCIES

SIGNED BY

DATE March 12, 1973

Keith L. Sackett

APPROVED AND SIGNED BY

*Arthur O. Enger*  
\_\_\_\_\_  
Arthur O. Enger

DATE March 12, 1973

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO.

13581