

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 48 N. R. 32 <del>XX</del> W.	I 7 & I 8
2. PROPERTY CONTROLLING IN SECTION	22, T. 48 N. R. 32 <del>XX</del> W.	2 & 7
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER \_\_\_\_\_

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- Corners I 7 & I 8:** Original posts or accessories not found. Found sq. wood post N6½°E 38.9 ft. for approx. Corner I 7, and found sq. wood post N7°E 33.4 ft. for approx. Corner I 8.
  - Corner 2:** Not established in original survey; found a sq. wood post N36°W 4.3 ft. for approx. corner.
  - Corner 7:** Not established in original survey nor subsequently, apparently.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- Corner I 7:** The found post not agreeing with a statement in original field notes that corner was located in a swamp edge, the corner was re-established on 9/23/71 by double proportionate measurement, at which point it does fall in a swamp edge.
  - Corner I 8:** Found nothing to support the found post; therefore, on 10/4/71 re-established the corner on line between section corners 39.839 ch. to N and to S.
  - Corner 2:** Established 9/22/71 on line between Sec. Cor. 19.991 ch. E and 1/4 corner 19.991 ch. W.
  - Corner 7:** Established 10/4/71 on line between Sec. Cor. 19.919 ch. N and 1/4 cor. 19.919 ch. S.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- Witnesses for Corner I 7:**
    - B. Spruce 4 S56°W (mag.) 36.6 ft. "S22, NBT"
    - B. Spruce 8 S21°W (mag.) 15.7 ft. "S23, NBT"
    - W. Pine 24 N17°W (mag.) 55.0 ft. "S15, NBT"
  - Witnesses for Corner I 8:**
    - Sugar Maple 6 S70°W (mag.) 14.1 ft. "1/4S, NBT"
    - Sugar Maple 6 S50°E (mag.) 14.4 ft. "1/4S, NBT"
  - Witnesses for Corner 2:**
    - Sugar Maple 5 N25°E (mag.) 44.5 ft. "1/16S, BT"
    - Sugar Maple 10 S23°W (mag.) 21.5 ft. "1/16S, BT"
  - Witnesses for Corner 7:**
    - B. Spruce 10 S56°E (mag.) 16.7 ft. "1/16S, BT"
    - B. Spruce 11 N80°E (mag.) 16.8 ft. "1/16S, BT"

**Monuments for all four corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Keith L. Sackett CHIEF OF SURVEY PARTY DATE March 12, 1973

APPROVED AND SIGNED BY Arthur O. Enger MICHIGAN REGISTERED LAND SURVEYOR DATE March 12, 1973 (SEAL)

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581