

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—	LOCATED IN—	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY	T. 48 N. R. 32 <del>XX</del> W.	I 6	REGISTER OF DEEDS STAMP AND FILING NUMBER
2. PROPERTY CONTROLLING IN SECTION	14 T. 48 N. R. 32 <del>XX</del> W.	3 & 10	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. W.		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on September 28 1971, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner I 6:** Original post or accessories not found. No subsequent monuments found.

**Corners 3 & 10:** Not set in original survey or subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner I 6:** Re-established on line between section corners 39.780 ch. to N and to S.

**Corner 3:** Established on line between section corner 19.890 ch. N and 1/4 corner 19.890 ch. S.

**Corner 10:** Established on line between section corner 19.890 ch. S and 1/4 corner 19.890 ch. N.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Monuments for all three corners:** 1: I.D. x 36" iron pipe with 4" aluminum cap.

**Witnesses for Corner 16:** W. Spruce 6 S30°E (mag.) 11.7 ft. "1/4S, NBT"  
Maple 5 N47°W (mag.) 12.6 ft. "1/4S, NBT"

**Witnesses for Corner 3:** Spruce 10 N26°E (mag.) 3.8 ft. "1/16S, BT"  
Tamarack 11 S43°E (mag.) 12.8 ft. "1/16S, BT"

**Witnesses for Corner 10:** Tamarack 14 N55°E (mag.) 36.7 ft. "1/16S, BT"  
Maple 6 S22°W (mag.) 12.3 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE March 13, 1973

APPROVED AND SIGNED BY Keith L. Sackett CHIEF OF SURVEY PARTY DATE March 13, 1973

*Arthur O. Enger*  
MICHIGAN REGISTERED LAND SURVEYOR  
**Arthur O. Enger**

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581