

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 48 N. R. 32 W.	J 9
2. PROPERTY CONTROLLING IN SECTION	T. 48 N. R. 32 W.	10 & 15
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19___, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19___, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner J9: Original post or accessories not found. Found a sq. wood post in place as set by unknown surveyor.

Corner 10: Not established in original survey. Found a sq. wood post N36°E 11.4 ft. for an approx. corner.

Corner 15: Not established in original survey. Found an 8" cedar with a location poster on it N16°E 25.9 ft., indicating the approx. corner location.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner J9: As the found post is on line between original section corners 40.458 ch. to E and to W, accepted it and placed new monument on 9/28/71.

Corner 10: Established 10/4/71 on line between Sec. Cor. 19.919 ch. S and 1/4 corner 19.919 ch. N.

Corner 15: Established 9/30/71 on line between Sec. Cor. 20.229 ch. W and 1/4 corner. 20.229 ch. E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all three corners: 1" I.D. x 36" iron pipe with 4" aluminum cap

Witnesses for Corner J9: B. Spruce 6 S 2°E (mag.) 14.6 ft. "1/4S, NBT"
Cedar 7 S36°W (mag.) 42.0 ft. "1/4S, NBT"

Witnesses for Corner 10: B. Spruce 8 N13°W (mag.) 14.0 ft. "1/16S, BT"
Tamarack 6 S56°E (mag.) 21.1 ft. "1/16S, BT"

Witnesses for Corner 15: Cedar 10 S12°E (mag.) 5.5 ft. "1/16S, BT"
Cedar 7 N11°E (mag.) 18.8 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES.

SIGNED BY Keith L. Sackett CHIEF OF SURVEY PART DATE March 9, 1973

APPROVED AND SIGNED BY Arthur O. Enger DATE March 9, 1973
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581