

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY	T. 48 N. 32 R. 32 <sup>XXX</sup> <sub>W.</sub>	J7, K6, & K7	
2. PROPERTY CONTROLLING IN SECTION	14 T. 48 N. 32 R. 32 <sup>XXX</sup> <sub>W.</sub>	16	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. 1. W.		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on see below 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corners J7, K6, & K7:** Original post or accessories not found. At J7, no subsequent monument found. At K6, found a sq. wood post N70°W 43.2 ft. set by L. Stevens, Area Forester, DNR for an approximate corner. At K7, found a 2"x2"x4' sq. post S74°E 1.165 ch. from corner, set by unknown party, and a 4"x4"x6' sq. cedar post N76°E .645 ch. from corner, set by L. Stevens for an approximate corner.

**Corner 16:** Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner J7:** Re-established on 10/8/71 on line between Sec. Corners 39.974 ch. to E and to W.  
**Corner K6:** Re-established on 10/21/71 on line between Sec. Corners 39.979 ch. to N and to S.  
**Corner K7:** Re-established on 5/6/71 by double proportionate measurement between corners 79.90 ch. N, 79.99 ch. S, 79.95 ch. E, and 79.95 ch. W.  
**Corner 16:** Established 5/6/71 on line between Sec. Cor. 19.985 ch. E and 1/4 corner 19.985 ch. W.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Monuments for all four corners:** 1" I.D.x36" iron pipe with 4" aluminum cap.  
**Witnesses for Corner J7:** Tamarack 8 N55°E (mag.) 8.2 ft. "1/4S, NBT"  
 B. Spruce 8 S46°W (mag.) 21.6 ft. "1/4S, NBT"  
**Witnesses for Corner K6:** Y. Birch 12 N85°W (mag.) 6.7 ft. "1/4S, NBT"  
 Sugar Maple 5 S34°E (mag.) 13.1 ft. "1/4S, NBT"  
**Witnesses for Corner K7:** Red Maple 6 N86°W (mag.) 8.8 ft. "S14, NBT"  
 Red Maple 5 N77°E (mag.) 21.5 ft. "S13, NBT"  
 Sugar Maple 8 S61°E (mag.) 9.3 ft. "S24, NBT"  
**Witnesses for Corner 16:** W. Spruce 10 N12°W (mag.) 15.1 ft. "1/16S, BT"  
 Sugar Maple 5 S29°E (mag.) 15.2 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE March 9, 1973  
 APPROVED AND SIGNED BY Keith L. Sackett CHIEF OF SURVEY PARTY DATE March 9, 1973  
Arthur O. Enger MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581