

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T48 N. NR. 32 W. . .

Baraga

COUNTY

DESCRIPTION OF CORNER Section Corner common to Sec.'s 9-10-15-16

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 10" W. Pine N 75° E 41 links

"S 10 NBT"

9" Soft Maple S 14° W 48 links

"S 16 NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced corner from one yellow birch stump bearing N 62° W 60 links.

Traces of notch and several axe marks. Found remains of yellow birch stump S 69° E 31 links.

Several old cruisers blazes in area. Cedar post in place.

Found by Forestry Division Survey Crew.

SURVEYORS SEAL

SIGNED

Billy D. Buckles
REGISTERED LAND SURVEYOR

DATE 8/7/57