

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. ~~48-49~~ NR 32-33 W.

----- Baraga -----

----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sec.'s 6-1-36-31
Also corner common to 4 Townships -----

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER 12" Cedar S 52° W 49 links
"S 1 NBT" -----

12" W. Pine N 18° E 121 links
"S 31 NBT" -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Set corner at intersection of blazed lines. Found numerous blazes and cruisers names at corner location.

Found 15" Cedar bearing S 40° W, 43 links.
This tree is scribed "R 39 W T 48 N S1". This tree appears to be as old as the original survey. Could find no record of such tree.

Found no absolute evidence of original B.T.'s.

Corner lies at North end of winter road.

Found by L. Stevens, District Forester.

Corner placed and witnessed Dec. 10, 1957.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 12/19/57-
REGISTERED LAND SURVEYOR