

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 48. NR. 32. W.

B a r a g a COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 15, 16, 21, 22

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap.

WITNESSES TO CORNER 7" Cedar (S 22 NBT) S 28° E 42 1/2 Links

6" B. Spruce (S 16 NBT) N 40° W 11 1/2 Links

8" B1 Spruce (S 15 NBT) N 19° E 47 1/2 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from old Spruce Witness Tree (not recorded) found this tree down and in poor condition. Scribe marks "S 21" bearing S 03° W 18 Links. Fould old blazes facing forner.

Corner was placed and witnessed February 10, 1960.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 4/29/60  
REGISTERED LAND SURVEYOR  
Billy D. Buckler