


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES
LAND CORNER RECORD

Baraga COUNTY
T 48N R 31-32W

DESCRIPTION OF CORNER Section Corner 1, 6, 7, and 12
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED July 17, 1969
WITNESSES TO CORNER..... Y. Birch 18 S42°E 17 lks. "S7, NBT"



Sugar Maple 10 N25°W 23½ lks. "S1, NBT"
Hemlock 9 S49°W 46 lks. "S12, NBT"
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed from two original BT's, both green; a Y. Birch 9 N42E 19 and a Y. Birch 12 S35W 24. Northeast BT is now 32" in diameter, with an open seam facing SW and with remnants of the original faces and traces of scribe marks "BT" visible inside the tree at about where 9" diameter would be. Many old blazes with cruisers' names on the tree. Southwest BT is now about 23" diameter, with old rotted out choppings on an inside face, facing NE. Also found a scribed cedar post rotted off and lying on ground. Corner lies just below the top of a hill and agrees with original field note call to descend west from corner. Post had apparently been re-witnessed by unknown surveyor many years ago.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

1/28/71

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68