

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Baraga COUNTY
T 48N R 32 W

DESCRIPTION OF CORNER 1/4 corner between Sections 1 and 2

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED December 2, 1970

WITNESSES TO CORNER..... Y. Birch 14 N87°E (magnetic) 39.2 ft. "1/4S, NBT"



Y. Birch 11 S86°W (magnetic) 44.3 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established by proportionate measurement on line between section corner 39.435 ch. south and section corner 38.645 ch. north.

Variation is about 1°00' West.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

August 31, 1971

Arthur O. Enger

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68