


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Baraga COUNTY
T 48 N R 32 W

DESCRIPTION OF CORNER Section Corner 10, 11, 14, and 15
CORNER MONUMENT 1" I.D. x 48" iron pipe with 4" brass cap.
DATE MONUMENT PLACED AND WITNESSED November 19, 1970
WITNESSES TO CORNER..... B. Spruce 5 S64°E 21.8 ft. "S14, NBT"



B. Spruce 9 S30°W 32.8 ft. "S15, NBT"
B. Spruce 7 N82°W 27.3 ft. "S10, NBT"
AND All bearings are magnetic.

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established by double proportionate measurement from corners 1 mile N, 2 miles S, 1 mile E, and 1 mile W. Corner position agrees with swamp edge to west but not to south, reinforcing the undersigned's belief that only the original field notes for the E and W lines in this area are reliable.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

November 19, 1970

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68