

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Baraga COUNTY  
T 48N R 32W

DESCRIPTION OF CORNER South 1/16 corner between Sections 10 and 11

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED December 3, 1970

WITNESSES TO CORNER..... W. Spruce 9 N32°E (magnetic) 13.7 ft. "1/16S, BT"



B. Spruce 6 S64°W (magnetic) 13.0 ft. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

No evidence that the corner had been established previously.

Corner established on line between section corner 19.891 ch. south and  
1/4 corner 19.891 ch. north.

Variation about 0°00'.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

DATE September 22, 1971

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68