

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Baraga COUNTY
T 48N R 32W

DESCRIPTION OF CORNER North 1/16 corner between Section 10 and 11

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED December 3, 1970

WITNESSES TO CORNER..... Tamarack 3 S10°E (magnetic) 25.7 ft. "1/16S, BT"



B. Spruce 6 N72°W (magnetic) 69.8 ft. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

No evidence that the corner had been established previously.

Corner established on line between section corner 19,891 ch. north and 1/4 corner 19,891 ch. south. Note: original field notes call for a "stream 40 links wide runs SE" 1.00 ch. south of this corner. There is no such stream, leading the undersigned to the conclusion that this section line may never have been run in the original survey.

SURVEYOR'S SEAL

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE September 22, 1971

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68