

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Baraga COUNTY
T 48N R 31-32W

DESCRIPTION OF CORNER South 1/16 corner between Section 7 and 12

CORNER MONUMENT 1" I. D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED December 16, 1970

WITNESSES TO CORNER..... B. Spruce 4 S24°W (magnetic) 8.5 ft. "1/16S, BT"



B. Spruce 4 N65°W (magnetic) 11.2 ft. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

No evidence that the corner had been established previously.

Corner established by proportionate measurement on line between an original section corner 19.871 ch. south and an original line tree stump 11.694 ch. north. Record distance south to swamp edge is 50 links, actual distance is 56 links, but original measurements were only recorded to nearest half-chain.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

September 22, 1971

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68