

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Baraga COUNTY
T 48N R 31-32W

DESCRIPTION OF CORNER 1/4 corner between Sections 7 and 12

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED November 4, 1969

WITNESSES TO CORNER..... W. Birch 14 West (magnetic) 10 lks. "1/4S, NBT"



Balsam 6 S3°E (magnetic) 10 lks. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established by proportionate measurement on line between an original line tree stump 8.145 ch. south and an original section corner 39.585 ch. north. Corner is 15 links north of UPPCo. R.O.W.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

September 22, 1971

Arthur O. Enger

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68