

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Baraga COUNTY
T 48N R 32W

DESCRIPTION OF CORNER 1/4 corner between Sections 12 and 13

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED June 17, 1970

WITNESSES TO CORNER..... Red Maple 11 S35°W (magnetic) 12.1 ft. "1/4S, NBT"



Sugar Maple 12 N42°W (magnetic) 28.0 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established on line between section corners 40.20 ch. to east and to west. Not satisfied that this is near the original corner position, because of doubts as to authenticity of the found section corner to the west. Since the latter has been long accepted as the section corner, the implication is that this position for the dependent 1/4 corner must also be accepted.

Variation about 1°00' West.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE September 22, 1971

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68