

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Baraga COUNTY
T 48N R 32W

DESCRIPTION OF CORNER 1/4 corner between Sections 11 and 12

CORNER MONUMENT 1" I. D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED June 18, 1970

WITNESSES TO CORNER..... W. Birch 8 S71°W (magnetic) 32.9 ft. "1/4S, NBT"



W. Spruce 8 S61½°E (magnetic) 83.0 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 2" O.D. x 6" iron pipe N77½°W 47.4 ft. from corner. No evidence or testimony to support it. A local informant claims he has seen this pipe at different locations in the vicinity during his long residency in the area, but the undersigned has no personal knowledge that this is true.

Corner re-established (or possibly established for the first time) on line between section corners 39.435 ch. to north and south. Original field notes call for a "stream 40 links wide runs East" 1.36 ch. north of corner, but no such stream exists now or appears ever to have existed, leading to the suspicion that the line may never have been run at the time of the original survey. The midpoint position of this section line falls in a stream four links wide running northeast, in a swamp. Original notes say corner was on upland.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE September 22, 1971

Arthur O. Enger

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68