

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 48 N. R. 32 E. W.	E2
2. PROPERTY CONTROLLING IN SECTION 4	T. 48 N. R. 32 E. W.	10
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 3, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on October 3, 1978, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
 Corner E2: Original Monument and Accessories Not Found. Corner was placed in tag alder low land and no original bearing trees were witnessed.
 Corner 10: Not Set on Original Survey Nor Subsequently Apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 Corner E2: Restored on line and by proportion between corners north and south.
 Corner 10: Established on line between corners north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Corner E2: Set 1" I.D. x 36" Iron Pipe with 4" aluminum cap in tag alder near bayou.
 9" Spruce N28W 38.5 ft. 1/4S, BT
 Corner 10: Set 1" I.D. x 36" Iron Pipe with 4" aluminum cap.
 5" Sugar N30W 18.0 ft. 1/16S, BT
 5" Sugar S55W 14.9 ft. 1/16S, BT
 6" Sugar N75E 14.1 ft. 1/16S, BT

SIGNED BY _____ DATE _____


SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE October 24, 1978

CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
Keith L. Sackett
Department of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006