

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 48 N. 32 E. R. 32 W.	E1
2. PROPERTY CONTROLLING IN SECTION 4	T. 48 N. 32 E. R. 32 W.	3
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 4, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on October 4, 1978, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 3: Not Set on Original Survey Nor Subsequently Apparently.

Corner E1: Original Monument and Accessories Not Found. Found old rotted post remains in a pile of rocks. Found Celotex location poster in dead 5" Spruce N59W 15.4 ft.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 3: Established on line and by proportion between corners north and south.

Corner E1: Restored at old post location. Fits good with corners east and west and swamp edge south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 3: Set 1" I.D. x 36" Iron Pipe with 4" aluminum cap.

4" Spruce S55W 13.4 ft. 1/16S,BT

6" Spruce N54W 21.6 ft. 1/16S,BT

6" Spruce N76E 12.1 ft. 1/16S,BT

Corner E1: Set 1" I.D. x 24" Iron Pipe with 4" aluminum cap.

9" Spruce N18E 15.0 ft. S33,NBT

9" Spruce S35E 19.7 ft. S4,NBT

6" Spruce N42W 32.5 ft. S32,NBT

SIGNED BY _____ DATE _____


SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE October 8, 1978

CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
Keith L. Sackett
Department of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006