

BARAGA Co.

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF -:	LOCATED IN -:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 48 N. R. 32 X. W.	G2
2. PROPERTY CONTROLLING IN SECTION	4 T. 48 N. R. 32 X. W.	10, 3
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO.	RECORDED PLAT	
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 29, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on August 29, 1978, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

**Corner G2: Original Monument and Accessories Not Found.**

**Corner 10: Not set on original survey nor subsequently apparently. Corner falls 1/2 CH east and 1/2 CH south of old logging read.**

**Corner 3: Not set on original survey nor subsequently apparently.**

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

**Corner G2: Corner restored on line and by proportion between section corners.**

**Corner 10: Established midway and on line between corners north and south.**

**Corner 3: Established on line and by proportion between corners north and south.**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**Corner G2: Set 1" I.D. by 36" Iron Pipe with 4" aluminum cap.**

5" Sugar N34E 14.7 ft. 1/2 S, NBT

7" Maple S78W 27.1 ft. 1/2 S, NBT

10" Maple S19E 32.4 ft. 1/2 S, NBT

**Corner 10: Set 1" I.D. by 36" Iron Pipe with 4" aluminum cap.**

12" Aspen N68W 51.1 ft. 1/16 S, BT

6" Spruce N25E 69.8 ft. 1/16 S, BT

**Corner 3: Set 1" I.D. by 36" Iron Pipe with 4" aluminum cap.**

16" Cedar N46E 39.8 ft. 1/16 S, BT

4" Balsam N66W 7.9 ft. 1/16 S, BT

6" Maple S61W 27.9 ft. 1/16 S, BT

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE August 30, 1978

CHIEF OF SURVEY PART  
MICHIGAN REGISTERED LAND SURVEYOR  
**Keith L. Sackett**  
Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006