

BARAGA Co.

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 48 N. R. 32 E. W.	61, C2
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 29, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
 Corner C1: Found old post in a rock pile that fits good with land calls N-S-E-W, and possible line tree west.

Corner C2: Original Monument and Accessories Not Found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 Corner C1: Restored at old post in pile of rocks.

Corner C2: Restored corner on line by proportion between corners north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Corner C1: Set 1" I.D. x 36" Iron Pipe with 4" aluminum cap.
 5" Yellow Birch N63W 5.9 ft. S31,NBT
 7" White Pine N78E 6.0 ft. S32,NBT
 12" Balsam S75W 11.6 ft. S6,NBT
 Corner C2: Set 1" I.D. x 36" Iron Pipe with 4" aluminum cap in Tag Alder bottom
 4" Balsam N80E 22.2 ft. 1/4S,NBT
 8" Yellow Birch S28E 46.8 ft. 1/4S,NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett
 Department of Natural Resources
 DATE 10/27/78

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

