

BARAGA Co

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 48 N. 32 E. W.	D5
2. PROPERTY CONTROLLING IN SECTION 17	T. 48 N. 32 E. W.	2, 1
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 5, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner D5: Original Monument and Accessories Not Found.
 Corner 2: Not Set on Original Survey Nor Subsequently Apparently.
 Corner 1: Not Set on Original Survey Nor Subsequently Apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner D5: Restored on line and midway between section corners.
 Corner 2: Established on line between section corner east and $\frac{1}{2}$ corner west.
 Corner 1: Established on line between section corner west and $\frac{1}{2}$ corner east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner D5: Set 1" I.D. x 36" Iron Pipe with 4" aluminum cap and cedar post in small creek in a Tag Alder swamp. No available N.B.T.'s.	Corner 1: Set 1" I.D. x 36" Iron Pipe with 4" aluminum cap.
Corner 2: Set 1" I.D. x 36" Iron Pipe with 4" aluminum cap.	12" Sugar N51E 23.5 ft. 1/16S,BT
12" White Pine N16E 9.1 ft. 1/16S,BT	12" Sugar N64W 12.6 ft. 1/16S,BT
12" White Pine N75W 27.8 ft. 1/16S,BT	9" Sugar S01W 4.7 ft. 1/16S,BT
9" White Pine S78W 38.9 ft. 1/16S,BT	

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 10/26/78
 CHIEF OF SURVEY PARTY
 REGISTERED LAND SURVEYOR
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

