

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 48N R 32W	65
	T R	
	T R	
	T R	
2. Property Controlling In Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp &amp; File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Apr 22 1998

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:


NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:  
(65) Corner common to Sections 9-10-15-16. Corner re-monumented at the original position by Billy D. Buckler in 1957: "Replaced corner from one yellow birch stump bearing N62W 60 links. Traces of notch and several axe marks. Found remains of yellow birch stump S69E 31 links. Several old cruisers blazes in area. Cedar post in place. 1" pipe with 4" brass cap. Witnesses: 10" W. Pine N75E 41 links, 9" Soft Maple S14W 48 links".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
(65) Recovered the 1957 monument, a 1" 10 iron pipe capped with a 4" dia. brass Michigan Dept. of Conservation tablet, in good condition, and at record bearing and distance from both of the 1957 witnesses, in good condition. The remains of the Y. Birch noted in the 1957 record N62W were recovered at record bearing and distance. Left the monument in place and marked two new witnesses as described below. Corner recovered and re-witnessed by B. Wheeler and D. Lampela, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
(65) Found 1" pipe with 4" brass cap.  
The 1957 witnesses are as recorded.  
Blazed and scribed the following new bearing trees:  
12" W. Spruce N18E 20.9' "S10 NBT"  
6" Maple N29W 19.9' "S9 NBT"  
Bearings are magnetic. Distances to notch in lower blaze.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 6/11/98

For the Michigan Department of Natural Resources - Forest Management Division