

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 32W	G7
	T 48N R 32W	F5
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Apr 27 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(G7) Corner common to Sections 15-16-21-22. Corner reestablished in 1960 by Billy D. Buckler, RLS: "This corner was replaced from old Spruce Witness Tree (not recorded). Found this tree down and in poor condition. Scribe marks "S 21" bearing S03W 18 links. Found old blazes facing corner. Corner monument 1" pipe with 4" brass cap. Witnesses to corner 7" Cedar S28E 42.5 links, 6" B. Spruce N40W 11.5 links, 8" B. Spruce N19E 47.5 links". Found no subsequent record.

(F5) Quarter corner common to Sections 9-16. Corner reestablished in 1975 by Keith L. Sackett by single proportionate measurement between Section corner East and West. 1" I.D. x 36" iron pipe with 4" aluminum cap. 14" Sugar S82E 27.3', 18" Y. Birch N02E 21.1', 14" Spruce marker tree S69W 3.9'. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G7) The 1960 monument was not recovered. Remonumented the corner in the 1960 position at record bearing and distance from the three 1960 witnesses, all recovered. The B. Spruce NW was recovered in good condition with blazes guaged over. The measuring notch is visible. The B. Spruce NE is a standing dead stub. The Cedar is in good condition with scribing visible. At the position for the corner, I placed a 1" ID x 32" iron pipe set in a 2' dia. by 1' high rock mound and capped with a 4" cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by B.Wheeler and D.Lampela, Baraga District Office.

(F5) Recovered the 1975 monument, as described, a 1" ID iron pipe capped with a 4" dia. cast aluminum State of Michigan tablet, in good condition, and at record bearing and distance from the 1975 accessories, all recovered in good condition. Left the monument in place and marked two new bearing trees as described below. Corner recovered and rewitnessed by D.Lampela and B.Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G7) Set 1" iron pipe with 4" MDNR cap.

Blazed and scribed the following:

6" B. Spruce N65E 39.2' "S15 NBT"

8" Cedar S49W 35.3' S21 NBT"

The 1960 NBTs:

8" B. Spruce N34W 7.7'

9" Cedar S23E 28.0'

Bearings are magnetic. Dist. to notch in lower blaze. Placed squared balsam post adjacent.

(F5) found 1" pipe with 4" MDNR cap.

Blazed and scribed the following new

bearing trees:

10" Y. Birch S35W 15.1' "1/4S NBT"

17" Sugar N65W 40.1' "1/4S NBT"

The 1975 witnesses are as previously

recorded. Bearings are magnetic.

Distances to notch in lower blaze.



Signed by

Stephan J. Szyszkoski

Date

6/10/98

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division