

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga (County)	Located in:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>16</u> T <u>48N</u> R <u>32W</u>	<u>16</u>
	S <u>16</u> T <u>48N</u> R <u>32W</u>	<u>4</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Apr 28 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(16-Sec. 16) East 1/16 corner, Section 16. Corner not established in the original survey. Found no subsequent record.
(4-Sec. 16) Northwest 1/16 corner, Section 16. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(16-Sec. 16) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a line of mean true bearing between Quarter corner 1313.17' West and Section corner 1313.17' East. At the position for the corner I placed a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by B.Wheeler and D.Lampela, Baraga District Office.

(4-Sec. 16) Found no evidence of prior monumentation at the corner position. Established the corner at the intersection of straight lines connecting opposite 1/16 corners. At the position for the corner I placed a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(16) Set 1" pipe with 4" MDNR cap.
Blazed and scribed the following:
5" Maple S11E 23.85' "S1/16 BT"
8" Maple in clump S64W 33.15' do
6" Maple N09E 13.25' "S1/16 BT"
8" W. Birch S88E 31.35' "S1/16 BT"
Placed squared maple post adjacent.
Bearings are magnetic. Distances to notch in lower blaze.

(4) Set 1" pipe with 4" MDNR cap.
Blazed and scribed the following:
10" Tamarack N80E 17.0' "NW1/16 BT"
8" Cedar S04W 9.0' "NW1/16 BT"
6" Cedar S56W 8.8' "NW1/16 BT"
7" Cedar N07W 20.8' "NW1/16 BT"
Bearings are magnetic. Distances to notch in lower blaze. Placed a squared tan. post adjacent.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 6/10/98

For the Michigan Department of Natural Resources - Forest Management Division