

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>32W</u>	<u>F6</u>
	T <u>48N</u> R <u>32W</u>	<u>G6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Apr 30 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(F6) Center of Section 16. Corner not established in the original survey. Found no subsequent record.
 (G6) Quarter corner common to Section 15-16. Corner reestablished in 1975 by Keith L. Sackett by single proportionate measurement between section corners north and south. Set 1" I.D. x 36" iron pipe with 4" aluminum cap. 13" Sugar N40W 10.7', 6" Sugar S77E 7.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F6) Found no evidence of prior monumentation at the corner position. Established the corner at the intersection of straight lines connecting opposite quarter corners. At the position for the corner I placed a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by B.Wheeler and D.Lampela, Baraga District Office.
 (G6) Recovered the 1975 monument as described, a 1" ID iron pipe capped with a 4" dia. cast aluminum State of Michigan tablet, in good condition, and at record bearing and distance from the 1975 witnesses, both recovered in good condition. Determined the monument to be 0.12' South and 0.57' East of the position intended in 1975. Accepted the monument as a careful and faithful reestablishment of the position of the original corner. Corner recovered and rewitnessed by D.Lampela and B.Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F6) Set 1" pipe with 4" MDNR cap.
 Blazed and scribed the following:
 10" Maple N74W 5.95' "CS BT"
 7" Maple N06E 15.25' "CS BT"
 4" Spruce S82E 20.5 "CS BT"
 12" Maple S09W 36.05' "CS BT"
 Placed a squared maple post adjacent.
 Bearings are magnetic. Distances to notch in lower blaze.

(G6) Found 1" pipe with 4" alum. cap.
 Blazed and scribed the following:
 8" Sugar N14E 12.55' "1/4S NBT"
 The 1975 witnesses:
 14" Sugar N38W 10.7' "1/4S NBT"
 10" Sugar S75E 7.0' "1/4S NBT"
 Placed PK nail and washer in E. face power pole S30W 52.0' (slope dist).
 Placed squared post adjacent to cor.
 Bearings are magnetic. Distances to notch in lower blaze of trees.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/10/98

For the Michigan Department of Natural Resources - Forest Management Division