

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

62.

For corners in
Baraga

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>32W</u>	<u>A9</u>
	T <u>48N</u> R <u>32W</u>	<u>C13</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

C13 October 27, 1993

I, Stephan J. Szyszkoski, in a field survey on A9 November 02, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(A9) Section corner common to sections 19-30 T48N-R32W, and sections 24-25 T48N-R33W. Corner established in 1846 by Austin Burt. Original record shows 1) Cedar 10 S27E 15, 2) Cedar 10 N25W 7, 3) Spruce 12 S54E 27, 4) Cedar 14 N40E 52, 5) Spruce 8 S04W 8, 6) South 8.5 ch. leave swamp C. SE, 7) North 5.00 ch. Leave swamp, 8) East 3.00 ch. Leave swamp course N4S and enter high land.

(C13) Section corner common to Sections 31-32 T48N-R32W, and Sections 5-6, T47N-R32W. Corner perpetuated and recorded by Neal Sperhake RLS, in 1960, by a 1" iron pipe with an aluminum Kimberly-Clark Corp. cap placed from original bearing tree Sugar 12 S59E 15. Sperhake also found a Northern Paper Mills pipe with brass cap. NPM (now Ned Lake) records show that Sugar OBT S59E was found in 1939 with iron marks plain, and no trace of other OBTs. In 1954 NPM forester D.L. Buehl set a pipe at record bearing and distance from the Sugar OBT and marked two new BTs: Sugar 8 S81W 41, Sugar 10 N42E 50.5 links. Sperhake's 1960 NBTs: Maple 8 N30W 56 links, Maple 7 S60E 54 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A9) Original post not recovered. Accessories 1) through 5) referenced above were not recovered. Found corner location marked by 2 old squared posts, and a newer white C.F.I. post, the oldest post probably being in excess of 50 yrs. old. Two old cedar signature trees face the corner, the earliest observed date being 1933. A 1956 Celotex location poster and a second L.P. dated 1953 also face the corner. The posts check with the record as referenced in 6) through 8) above very well. Distance east to a probable original corner location at the section corner common to 20-21-28-29 checks with the record. Accepted the location of the posts as the best available evidence of the position of the original corner and monumented this position with a 1" I.D.x32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet.

(C13) Found and accepted a 1" pipe with 4" aluminum KC cap and a NPM pipe with 2" brass cap adjacent at record bearing and distance from the NBTs noted above. Maple N30W is still green and now 14" with blaze overgrown, Maple N42E is dead and down, Maple S60E observed to be S56E 35.2', a 13" tree with overgrown blazes, Maple S81W observed to be S84W 27.4' a dead stub with scribing visible. Marked 3 new bearing trees as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A9) Set 1" pipe with 4" aluminum cap. Blazed and scribed the following new bearing trees:

7" Cedar S35E 3.6' "S30 NBT"
7" Cedar N45E 9.8' "S19 NBT"
11" Cedar S34W 24.1' "S25 NBT"
12" Cedar N81W 32.8' "S24 NBT"
14" Cedar with location poster and old sig. tree, found squared S55W 7.7'
12" Cedar old sig. tree dated to 1933 N30E 13.9'

Set 4" squared cedar post adjacent.

Signed by _____

Stephan J. Szyszkoski

Date 11-17-93

Surveyor's Michigan License No. _____

33986

