

61.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Baraga

(County)	Located In:	Corner Code ##
1. Public Land Survey	T <u>48N</u> R <u>32W</u>	<u>C9</u>
	T <u>48N</u> R <u>32W</u>	<u>C8</u>
	T <u>48N</u> R <u>32W</u>	<u>D7</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

D7 October 28, 1993

C8 November 02, 1993

I, Stephan J. Szyszkoski, in a field survey on C9 November 02, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(C9) Section corner common to Sections 19-20-29-30. Corner established in 1852 by Guy H. Carleton. Original post referenced by the following bearing trees: Fir 8 N25 07 links, Spruce 10 S60E 07 links. Found no subsequent record.

(C8) Quarter corner common to Sections 19-20. Corner established in 1852 by Guy H. Carleton. Original post referenced by the following bearing trees: Spruce 6 N21W 19 links, Spruce 10 S17E 27 links. Found no subsequent record.

(D7) Quarter corner between Sections 17-20. Corner previously perpetuated by Neal Sperhake, RLS, 10-21-1960 and recorded in Baraga County Records as monumented by a 1" dia. x 3' long iron pipe with aluminum Kimberly-Clark Corp. cap placed from original bearing tree Maple 6 N87E 50. 1960 NBTs: Y. Birch 12 N7W 33 links "S17NBT", Maple 7 S10W 19 links "S20NBT". Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C9) Original post and accessories not recovered. Found no acceptable evidence of the position of the original corner. I note that the feature calls in the original notes for the lines North, South, East, and West from this corner appear to be inconsistent and unreliable. Reestablished the corner by double proportionate measurement to the original record between the nearest recovered/reestablished corners as follows: Section corner 4992.14' west, Section corner 5251.04' north, Section corner 5295.10' east, Section corner 10502.09' south. At the position for the corner, I placed a 1" I.D. x 72" iron pipe capped with a 4" dia. cast aluminum MDNR tablet. From the corner monumented, a 2"x2" post, painted white, apparently an approximate corner, bears S37W 25' distant.

(C8) Original post and accessories not recovered. Found no evidence of prior monumentation and no acceptable evidence of the position of the original corner. The corner falls in a leatherleaf bog characterized by small diameter tamarack. Few spruce are evident. Reestablished the corner midway and on a straight line between reestablished section corners 2625.52' north and south. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet.

(D7) Found and accepted the monument and accessories as described in the 1960 record. Noted new bearings to the NBTs and new diameters: Maple 12° S18W 12.5' meas., Y. Birch 14° N02W 21.4'. Marked two new bearing trees as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C9) Set 1" pipe with 4" aluminum cap. Blazed and scribed the following new bearing trees:

4" Tamarack S58W 18.1' "S30 NBT"
 5" Spruce N81W 18.6' "S19 NBT"
 12" Tamarack N80E 70.8' "S20 NBT"
 12" Cedar S62E 108.3' "S29 NBT"

Placed a squared and scribed post adjacent.

(C8) Set 1" pipe with 4" aluminum cap. Blazed and scribed the following new bearing trees:

5" Tamarack N66W 11.9' "1/4S NBT"
 3" Tamarack N08E 4.9' "1/4S NBT"
 3" Tamarack N62E 25.8' "1/4S NBT"
 5" Tamarack S12E 5.8' "1/4S NBT"

Placed a tamarack post 1' north of the corner.

(D7) Found 1" pipe with aluminum cap "Sperhake RLS 7876 10-21-60"

Blazed and scribed the following new bearing trees:
 5" Sugar N43E 14.2' "1/4S NBT"
 5" Maple N30W 16.2' "1/4S NBT"

Signed by

Stephan J. Szyszkoski

Date 11-17-93

Surveyor's Michigan License No. 33986

