

60.

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Biraga

(County)	Located in:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>32W</u>	<u>E6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>20</u> T <u>48N</u> R <u>32W</u>	<u>2</u>
	S <u>20</u> T <u>48N</u> R <u>32W</u>	<u>7</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Stephan J. Szyszkoski, in a field survey on October 28, 1993, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(E6) Quarter corner between Sections 20-21. Corner established in 1852 by Guy H. Carleton, Deputy Surveyor. Original post referenced by the following: Spruce 8 N88E 26 links, Spruce 14 S64W 39 links. Line notes show "Enter Swamp E8W" 1.06 ch. north of the corner. Found no subsequent record.

(2-Sec. 20) East 1/16 corner between Sections 17-20. Corner not set in original survey. Found no subsequent record.

(7-Sec. 20) North 1/16 corner between Sections 20-21. Corner not established in the original survey. Found no subsequent record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(E6) Original post and accessories not recovered. Found no evidence of prior monumentation. Found no acceptable evidence of the position of the original corner. Reestablished the corner midway and on a straight line between section corner 2637.10' north (being a perpetuated original corner) and section corner 2637.10' south (being a probable original corner location). At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet. The south edge of a swamp is north, 66' from the reestablished corner.

(2-Sec. 20) Found no evidence of prior monumentation. Established the corner midway and on a straight line between 1/4 corner 1324.34' west and section corner 1324.34' east. At the position for the corner, I placed a 1" x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet.

(7-Sec. 20) Found no evidence of prior monumentation. Established the corner midway and on a straight line between Section corner 1318.55' north and quarter corner 1318.55' south. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(E6) Set 1" pipe with 4" aluminum cap. Blazed and scribed the following new bearing trees:

14" Y. Birch N10W 5.8' "1/4S NBT"  
 18" Sugar S30E 22.9' "1/4S NBT"  
 10" Sugar S27W 42.0' "1/4S NBT"  
 12" Sugar S82W 43.5' "1/4S NBT"

placed a 4" squared sugar post 1' north of the corner.

A Champion location poster affixed to a 4" squared sugar, bears N28W 27.4' from the corner.

Signed by Stephan J. Szyszkoski

Surveyor's Michigan License No. 33986

(2) Set 1" pipe with 4" aluminum cap. Blazed and scribed the following bearing trees:

16" Cedar S64W 70.2' "1/16S BT"  
 16" Cedar N78W 141.0' "1/16S BT"  
 4" Balsam N41E 17.8' "1/16S BT"  
 10" Maple S54E 38.4' "1/16S BT"

placed a 5" squared cedar post 2' east of the corner. The corner is located 1 ft. north of a 5 link wide stream, course NW.

Date 11/17/93

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1979  
 REVISED MAY 14, 1979  
 REVISED JAN., 1983

