

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Baraga</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 48N R 32W	C2
	T _____ R _____	(GCDB 200640)
2. Property Controlling in Section	S 8 T 48N R 32W	2
	S _____ T _____ R _____	(GCDB 260600)
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	•	5		4		3		2		1		
3					•								
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 2 10/29/15 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(2-Sec. 8) East 1/16 corner between Sections 5 and 8. Not previously monumented.

(C2) Quarter corner common to Sections 5 and 6. 1977 - Reestablished by K.L.Sackett RLS on line and by proportion between corners north and south. Set 1"IDx36" Iron pipe with 4" aluminum cap in Tag Alder bottom. 4" Balsam N80°E 22.2'; 8" Y.Birch S28°E 46.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(2-Sec. 8) Established the position for the corner midway and on the Section line between Section corner 1317.85' east and Quarter corner 1317.85' west.

(C2) Found the 1977 monument in good condition and at record bearing and distance from the 1977 witnesses. The Balsam NE is a rotted stump. The Y.Birch SE is in good condition. The monument was found to be 5.94' north of the proportionate position intended in 1977, and 0.29' west of a straight line between C1 and C3. I accepted the monument as a careful and faithful reestablishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(2) Set 1"IDx28" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 3" Sugar N27°E 5.8' mrkd "1/16S BT"  
 12" Sugar S35°E 22.2' do  
 7" Sugar S52°W 15.7' do  
 8" Sugar N65°W 12.6' do  
 Squared a 2" sugar N48W 1.3' no nail.  
 E= 7898052.924 N= 200384.312

(C2) Found 1"ID Iron pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 11" Y.Birch S24°E 47.2' old blazes (1977 NBT)  
 5" Spruce N63°E 30.1' mrkd "1/4S NBT"  
 3" Spruce N83°E 15.9' do  
 5" Spruce N65°W 30.6' do  
 Set sq'd spruce post adjacent.  
 E= 7896863.264 N= 201212.647

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 data  
 Coord. Ref.=NGS PID1468: N= 199449.725 m. E= 7900599.998 m.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 03/18/2016

For the Michigan Department of Natural Resources, Forest Resources Division

