

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 32W	B5
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S T _____ R _____	_____
	S 18 T 48N R 32W	2
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5	●												
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 04/11/2012 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B5) Quarter corner common to Sections 7 and 18. 1852 - Established by Deputy Surveyor Guy H. Carleton 40.00 chains west of Section corner C5 and 35.30 chains east of Section corner A5. Set post. Cedar 12" N41W 16 links, Y.Birch 16" S58E 32 links.

(2-Sec. 18) East 1/16 corner between Sections 7 and 18. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B5) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the position for the corner on the Section line between Section corners 2338.63' west and 2650.00' east, being proportionate to the 1852 record.

(2-Sec. 18) Established the position for the corner midway and on the Section line between Section corner 1325.00' east and Quarter corner 1325.00' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 5" Balsam N31E 11.4' mrkd "1/4S NBT"
 5" Balsam N80E 19.9' do
 3" Balsam S28W 28.4' do
 3" Balsam N57W 29.9' do
 Set sq'd cedar post adjacent.
 Bearings are magnetic.

(2) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 5" B.Spruce N74E 23.95' mrkd "1/16S BT"
 5" Balsam S52E 17.35' do
 8" B.Spruce S50W 14.75' do
 4" W.Birch N50W 10.0' do
 Set sq'd cedar post adjacent.
 Bearings are magnetic.

Signed by *Stephan J. Szyszkoski*
 Surveyor's Michigan License No. 33986

Date 04/26/2012



For the Michigan Department of Natural Resources, Forest Resources Division