

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>14</u> T <u>48N</u> R <u>32W</u>	<u>16</u>
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 04 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.


A. Description of original monument and accessories and/or subsequent restoration:
 (16-Sec. 14) East 1/16 corner between Sections 14 and 23. Established in 1971 by A.O. Enger RLS on line between Section and 1/4 corners 19.985 ch. East and West. 1"IDx36" iron pipe. W.Spruce 10 N12W 15.1', Sugar Maple 5 S29E 15.2'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(16-Sec. 14) Recovered the 1971 monument in good condition and at record bearing and distance from the SE NBT maple, now 7" DBH, in good condition, with overgrown blazes. Left the monument in place and made new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(16) Found 1" ID iron pipe with 4" alum.
 MDOC cap. Blazed and scribed:
 3" Sugar S71W 38.1' "1/16S BT"
 15" Spruce N11W 21.3' do
 6" Sugar N74E 24.5' do
 7" Maple S24E 15.2' (the 1971 NBT)
 Found sq'd cedar post adjacent.
 Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/15/01

For the Michigan Department of Natural Resources - Forest Management Division