

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Baraga

(County)

Located In: Corner Code #

1. Public Land Survey	T <u>48N</u> R <u>32W</u>	<u>I3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

May 02 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3								●				
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

(I3) Corner common to Sections 2-3-10-11. 1971: Reestablished by A.O. Enger RLS at the proportionate position between corners 1 mile N, 2 miles E, 3 miles S, and river crossing 11.29 ch. W. Set 1"IDx36" iron pipe with 4" aluminum cap. W.Birch 10 N88E 20.6', W.Birch 10 S40 1/2W 43.4', Red Maple 4 N47 1/2W 18.6'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(I3) Found and accepted the 1971 monument in good condition and at record bearing and distance from the 1971 witnesses. The W.Birch E'ly and R.Maple NW are in good condition with overgrown blazes. The W.Birch SW is dead and down. The 1" pipe noted by Mr. Enger as being found S82 1/2E 31.0' from the corner was not recovered.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(I3) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nails in:  
 12" W.Birch S87E 20.9' old blazes \*  
 9" R.Maple N43W 18.6' old blazes \*  
 5" B.Spruce N11E 22.5' mrkd "S2 NBT"  
 5" B.Spruce S28E 21.9' mrkd "S11 NBT"  
 Set a sq'd spruce post adjacent.  
 Bearings are magnetic. Distances are to nail with tag. \* denotes 1971 NBT.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 6/13/05