

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T48N R 32W	M13
	T48N R 32W	K11
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

M13 Nov 20 2007
 K11 Oct 23 2007

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (M13) Corner to Townships 47-48N, Ranges 31-32W. 1846 - Established by Wm.A.Burt, Deputy Surveyor: Set Cedar post. Cedar 14 N36E 15 links, Cedar 10 S73W 21 links. Found no subsequent record.

(K11) Corner common to Sections 25-26-35-36. 1852 - Established by Guy Carleton, Deputy Surveyor. Set post. W.Pine 20 N18E 40 links, Aspen 18 S20W 44 links. 1960 - Remonumented by N.Sperhake RLS at original post fd. at record bearing and distance from W.Pine BT N18E 40 links. Found N.T.Thompson post, set about 1948, at the corner position. Set 1"x36" I.pipe with Kimberly-Clark Corp. cap. NBTs: W.Pine 7" N46W 28 links, Spruce 4" N28E 33 links, W.Birch 10" S66E 33 links, Spruce 5 S52W 51 links. See LCR Liber 2, Page 92.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (M13) Found a 1"ID I.pipe with 2 1/4" dia. brass tablet stamped "Northern Paper Mills 36/31/1/6", in good condition, not of record. From the monument, the remains of what may be the OBT Cedar N36E 15 links, now a 5' long cut cedar stub, lying on the ground, appearing to have fallen over in place, lie at record bearing and distance. No markings were found on this stub. Found woody debris and root holes at record bearing and distance for the OBT Cedar S73W 21 links, but these are not well defined. Found signature tree facing the monument with earliest visible date of 1940 and the letters "THOM" and what appears to be part of a "P", possibly the signature of N.T.Thompson RLS, who practiced in this area in the 1940's. Found two other living Cedars N30E and N66E with old markings and one dead Cedar East with double blazes facing the monument. An old sq'd post is adjacent to the monument. The monument was probably placed in 1954. NPM surveyors monumented and recorded corners 1/2 mile north and 1 mile east of this position in that year. Bearing and distance to corner F13 (nearest perpetuated original corner to the west) was found to be N89°56'49"W (true brg.) 18477.09' (Due West 18480.00=280.00 ch. GLO). I accept the monument as the best available evidence of the position of the original corner.

(K11) Found the Kimberly-Clark monument of record, in good condition, in a small mound of rock, and at record bearing and distance from what appear to be the rotted remains of the W.Pine BT N18E 40 links. The 1960 NBTs were not recovered. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (M13) Found 1"ID I.pipe with 2.25" dia. brass Northern Paper Mills cap. Set measuring nail with MDNR tag in the following:
 12" Cedar N30E 13.4' overgrown blazes found
 13" Cedar N66E 27.15' found scribing
 17" Cedar S29E 21.25' open blaze with signatures
 6" Cedar N43W 12.3' mrkd "S36 NBT"
 Bearings are magnetic.
 Set new sq'd cedar post adjacent.

(K11) Found 1"ID I.pipe with 4" alum. Kimberly-Clark Corp. cap RLS 7876. Set measuring nail with MDNR tag in the side of the following:
 8" Spruce N05E 42.0' mrkd "S25 NBT"
 11" Spruce N84E 32.4' do
 3" Tamarack S21W 41.3' "S35 NBT"
 7" Maple N83W 11.5' "S26 NBT"
 Set sq'd tamarack post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski Date 11/26/07

Surveyor's Michigan License No. _____

