

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T48N R 32W	E12
	T48N R 32W	J11
	T_____ R_____	_____
	S_____ T_____ R_____	_____
2. Property Controlling in Section	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____
3. Miscellaneous Property in Sec.	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

J11 Oct 23 2007
 E12 Oct 29 2007

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E12) Quarter corner common to Sections 32 and 33. 1852 - Established by Guy Carleton, Deputy Surveyor, midway and on the Section line between Section corners 39.94 chains north and south. Set post. BTs: Cedar 14 S63W 15 links, Cedar 4 N36E 7 links. Found no subsequent record.
(J11) Quarter corner common to Sections 26-35. 1852 - Established by Guy Carleton, Deputy Surveyor, midway and on the Section line between Section corners 39.915 chains east and west. Set post. BTs: Maple 6 N13E 33 links, Sugar 10 S38W 58 links. 1956 - Remonumented by Billy D. Buckler RLS: Replaced from 2 original BTs. One Maple (green); One Hard maple (down) in fair condition. Cedar stake in place. Tag on road 4 chains West placed by Celotex Corp. Set 1"ID I.pipe with 4" brass cap. 15" Soft Maple N58W 84 links to notch, 8" Cedar S35E 32 links to notch.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E12) The original post and accessories were not recovered. 1993 - The undersigned found an old squared and scribed wooden post with adjacent signature tree facing it, oldest observable signature dated 1940. 2007 - The post found in 1993 was recovered, now down and rotted. Signature tree S08W 7 ft. distant is a 15" cedar with old blaze facing the post position. The 1940 signature is evident but no longer readable. The post is located N 01 deg. 09'W (true) 2624.9' north of the Section corner E13 on the Township line and S 00 deg. 37'W (true) 7780.0' south of monumented E9. The original record between E9 and E13 is 159.76 chains (10,544.16'). Between these corners, I measure 2.11 chains shorter than record. Suspecting a blunder or other non-systematic deficiency in the original survey, I was reluctant to reject the post in favor of the proportionate position, especially so since the post appears to have satisfactorily marked the position of the corner for local landowners since at least 1940. I therefore accepted the post as the best available evidence of the position of the original corner and placed a monument at its position.
(J11) Found the 1956 monument in good condition and at record bearing from the 1956 NBT Maple NW, found at 32 links from the monument (the distance given in the record to the Cedar NBT: Distances on the record were likely transposed). The Cedar NBT SW was not recovered, it falling in a cleared area. Also found the rotting stump remains of the original BT Maple N13E, found at record bearing and distance, now a shell with no markings visible. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 8" Spruce N10W 17.45' mrkd "1/4S NBT" 8" Maple N65E 14.95' do 15" Cedar S08W 6.9' (the signature tree noted) 12" Cedar S59W 12.85' mrkd "1/4S NBT" Set sq'd cedar post adjacent. Bearings are magnetic.	(J11) Found 1"ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of: 26" Maple N56W 21.9' overgrown blazes (1956 NBT) 6" Sugar N15E 31.9' mrkd "1/4S NBT" 4" Sugar N88E 6.7' do 8" Maple S05W 5.0' do Set sq'd spruce post adjacent. Bearings are magnetic.
---	--

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

Signed by Stephan J. Szyszkoski Date 11/26/07

Surveyor's Michigan License No. _____

