

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Baraga

(County)

Located In:

Corner Code #

1. Public Land Survey

T ___ R ___
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling
 in Section

S 3 T 48N R 32W 4
 S 3 T 48N R 32W 3

3. Miscellaneous
 Property in Sec.

S ___ T ___ R ___
 S ___ T ___ R ___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Apr 26 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4	●●	3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(4-Sec. 3) Northwest 1/16 corner, Sec. 3. Not established in the original survey.

(3-Sec. 3) North 1/16 corner between Sections 3 and 4. 1978: Established by K.L. Sackett PS on line and by proportion between corners north and south. Set 1"IDx36" iron pipe with 4" aluminum cap. 16" Cedar N46E 39.8', 4" Balsam N66W 7.9', 6" Maple S61W 27.9'. It appears from the notes of the 1978 survey that Mr. Sackett used a record closing distance of 18.26 chains for his proportion rather than 18.46 as is shown on the plat.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(4-Sec. 3) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

(3-Sec. 3) Found and accepted the 1978 monument, at substantially the record position and at record bearing and distance from the 1978 witness trees. The Cedar NE is dead and down. The Maple is in good condition with overgrown blazes. The Balsam is in good condition with upper blaze overgrown, and scribing visible on lower blaze.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
 4" Maple S16E 12.1' mrkd "1/16S BT"
 9" Maple in clump N84E 5.1' do
 5" Cherry N52W 17.0' do
 5" Balsam N02W 10.6' do
 Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.

(3) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nails in:
 9" Maple S67W 28.0' old blazes *
 8" Balsam S60W 8.3' do *
 7" Spruce S89W 8.5' mrkd "1/16S BT"
 10" Spruce N20W 22.4' do
 Found cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. * denotes 1978 BT.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/13/05