

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	S <u>34</u> T <u>48N</u> R <u>32W</u>	<u>14</u>
2. Property Controlling in Section	S <u>34</u> T <u>48N</u> R <u>32W</u>	<u>12</u>
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on Oct 24, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 (14-Sec. 34) South 1/16 corner between Sections 34 and 35. Not established in the original survey.
 (12-Sec. 34) South 1/16 corner, Section 34. Not established in the original survey.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (14-Sec. 34) Established the corner midway and on the Section line between Quarter corner 1313.68' north and Section corner 1313.68' south.
 (12-Sec. 34) Established the corner midway and on a straight line between Center of Section 1316.03' north and Quarter corner 1316.03' south. From the position thus established, I found a 1" square iron pin, not of record, set by persons unknown, N24W, 37.6' distant, which I did not accept as marking the position for the corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (14) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 17" Maple S21W 17.85' mrkd "1/16S BT"
 4" Sugar N65W 14.0' do
 11" Spruce N41W 33.45' do
 12" Sugar N11E 33.85' do
 Set sq'd Cedar post adjacent.
 Bearings are magnetic.
 (12) Set 1"x32" I.pipe with 4" alum MDNR cap. Set measuring nail with MDNR tag in the side of:
 30" W.Pine N10W 44.0' mrkd "1/16S BT"
 11" Spruce N12E 32.6' do
 4" Tamarack S65E 22.2' do
 7" Spruce S31W 20.8' do
 Set sq'd cedar post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski Date 11/15/07

Surveyor's Michigan License No. 33986

