

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

|                                       |                         |               |       |
|---------------------------------------|-------------------------|---------------|-------|
| <u>Baraga</u><br>(County)             | Located In:             | Corner Code # |       |
| 1. Public Land Survey                 | T 48N R 32W             | E3            |       |
|                                       | T _____ R _____         | _____         | _____ |
|                                       | T _____ R _____         | _____         | _____ |
| 2. Property Controlling in Section    | S _____ T _____ R _____ | _____         | _____ |
|                                       | S _____ T _____ R _____ | _____         | _____ |
|                                       | S _____ T _____ R _____ | _____         | _____ |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____ | _____         | _____ |
|                                       | S _____ T _____ R _____ | _____         | _____ |
| 4. Lot No. _____, Recorded Plat _____ |                         |               |       |
| 5. Private Claims _____               |                         |               |       |

Register of Deeds Stamp & File Number

|    |    |   |    |   |    |   |    |   |    |   |    |   |   |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   | ●  |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

I, Stephan J. Szyszkoski, in a field survey on 11/06/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E3) Corner common to Sections 4-5-8-9. 1975 - Remonumented by K.L.Sackett RLS: Original monument and accessories not found. Found 1.25"IDx48" iron pipe witnessed by the M.S.H.D. in 1944 and used as corner for many years. Reestablished 6-19-75 at location of M.S.H.D. iron pipe. Set 1"IDx36" iron pipe with 4" aluminum cap. 18" Y.Birch S26W 16', 12" Sugar N36E 23.8', 5" Sugar N43W 10.5'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E3) Found the 1975 monument in position but bent over and with the cap broken off. The M.S.H.D. iron pipe, adjacent, was also found bent over. Removed the 1975 monument to find the lower portion vertical and undisturbed and at record bearing and distance from two remaining 1975 NBTs. The Y.Birch SW is in good condition and the Sugar NE is a dead stub. The third 1975 NBT was not recovered. Remonumented the corner at the 1975 position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E3) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 18" Y.Birch S30W 16.1' scribing plain (1975 NBT) 12" Maple N82W 57.7' mrkd "S5 NBT" 12" Maple N40E 24.3' "S4 NBT" 12" Maple S15E 12.0' "S9 NBT" Sq'd tamarack post adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 07/13/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities