

LAND CORNER RECORDATION CERTIFICATE
Feeling Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>4</u> T <u>48N</u> R <u>32W</u>	<u>10</u>
	S <u>4</u> T <u>48N</u> R <u>32W</u>	<u>3</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1					●								
2	6			5		4		3		2		1	
3					●								
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 12/03/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(10-Sec. 4) South 1/16 corner between Sections 4 and 5. 1978 - Established by K.L.Sackett RLS on line between corners north and south. Set 1"IDx36" Iron Pipe with 4" aluminum cap. 5" Sugar N30W 18.0', 5" Sugar S55W 14.9', 6" Sugar N75E 14.1'.

(3-Sec. 4) North 1/16 corner between Sections 4 and 5. 1978 - Established by K.L.Sackett RLS on line and by proportion between corners north and south. Set 1"IDx36" Iron Pipe with 4" aluminum cap. 4" Spruce S55W 13.4', 6" Spruce N54W 21.6', 6" Spruce N76E 12.1'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(10-Sec. 4) Found but did not accept the 1978 monument of record. The 1978 position was calculated and monumented in accordance with a position for Section corner E1 that was not correct and which has now been remonumented by the undersigned. Established the corner midway and on the Section line between Quarter corner 1320.62' north and Section corner 1320.62' south. The 1978 monument, found N41W 28.4' from the position established, was removed. The 1978 bearing trees are still in place, with overgrown blazes.

(3-Sec. 4) Found but did not accept the 1978 monument of record. The 1978 position was calculated and monumented in accordance with a position for the Section Corner E1 that was not correct and which has now been remonumented by the undersigned. Established the corner on the Section line between Quarter corner 1320.62' south and Section corner 1211.67' north, being proportionate to the original record. The 1978 monument, found N38W 73.9' from the position established, was removed. The 1978 bearing trees remain in place with overgrown blazes.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(10) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 9" Sugar N17E 17.35' mrkd "1/16S BT"
 9" Sugar S72E 19.35' do
 7" Sugar S09E 5.80' do
 5" Sugar S60W 25.35' do
 Set sq'd Tamarack post adjacent.
 Bearings are magnetic.

(3) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 8" Spruce N43E 16.6' mrkd "1/16S BT"
 9" Spruce N78E 15.9' do
 4" Spruce S16E 5.35' do
 6" Spruce N79W 2.1' do
 Sq'd cedar post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 07/13/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities