

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 32W	E2
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5	●	4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 12/03/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(E2) Quarter corner common to Sections 4 and 5. 1852 - Established by Guy Carleton Deputy Surveyor on the Section line 40.00 chains north of Section corner E3 and 38.35 chains south of Section Corner E1. Set post in Alder - "no trees for bearings". 1978 - Reestablished by K.L.Sackett RLS on line and by proportion between corners north and south. Set 1"IDx36" Iron Pipe with 4" aluminum cap in tag alder near bayou. 9" Spruce N28W 38.5'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(E2) The original post was not recovered. Found but did not accept the 1978 monument of record. The 1978 position was calculated and monumented in accordance with a position for Section Corner E1 that was not correct and which has now been remonumented by the undersigned. Reestablished the corner on the Section line and by proportionate measurement to the original record between Section corner 2641.24' south and Section corner 2532.29' north. The position for the corner falls in a alder bottom and was not monumented. Established and monumented a WITNESS CORNER on the Section line 95.00 feet north of the corner position. The 1978 monument was removed. The 1978 witness tree is in place with scar visible.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(E2) Set 1"IDx32" I.Pipe with 4" alum. MDNR cap stamped "WC 1/4S S5 S4 48N 32W PS33986 12-03-08" 95.00 ft. north of the corner position. Set measuring nail with MDNR tag in the side of:  
 5" Spruce S76W 21.2' mrkd "WC BT"  
 8" Spruce N20W 14.6' do  
 10" Spruce N36E 14.15' do  
 7" Spruce N56E 32.3' do  
 Set sq'd cedar post adjacent. Bearings magnetic.



Signed by Stephan J. Szyszkoski Date 07/13/2009  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities