

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 48N R 32W	H5
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5								●					
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 05/13/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H5) Quarter corner common to Sections 10 and 15. 1970 - A.O.Enger RLS monumented the corner on line between section corners 40.075 chains to east and west. Set 1"IDx36" I.pipe with 4" aluminum cap. W.Pine 14 S58W 60.1', W.Pine 14 S31W 28.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H5) Found the 1970 monument at record bearing and distance from the 1970 witnesses, now both stumps. The monument was found to have been installed in an erroneous position, 40' west of the proportionate position intended in 1970 and is not accepted. Reestablished and remonumented this date the position for the corner midway and on the Section line between Section corners 2643.22' east and west, proportionate to the original record. Removed the 1970 monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. The monument was made firm in a 3' dia. mound of rock. Set measuring nail/MDNR tag in:
 5" Tamarack N47E 37.1' mrkd "1/4S NBT"
 6" Balsam N58E 15.2' do
 7" Spruce S51E 42.3' do
 3" Balsam N62W 17.0' do
 Sq'd post adjacent. Bearings magnetic.



Signed by *Stephan J. Szyszkoski*
 Surveyor's Michigan License No. 33986

Date 05/28/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

Revised May 14, 1975

Revised Jan., 1983

Revised Oct., 1995