

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 32W	H7
	T 48N R 32W	I6
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on H7 03/17/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H7) Quarter corner common to Sections 15 and 22. 1963 - Corner remonumented by Billy D. Buckler RLS from OBT Tamarack in good condition. Set 1" I.pipe with 4" aluminum cap. 10" Cedar N5E 45 links, 10" B.Spruce S62W 6.5 links [record erroneously states 6.5"].

(I6) Quarter corner common to Sections 14 and 15. 1971 - Reestablished by A.O.Enger RLS midway and on line between Section corners 39.780 chains north and south. Set 1"ID x 36" I.pipe with 4" aluminum cap. W.Spruce 6" S30E 11.7', Maple 5" N47W 12.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H7) Recovered the 1963 monument in good condition, set very loosely and leaning. Straightened and reset the monument in accord with the distances to the two NBTs. The Cedar NE is in good condition with overgrown blazes, the Spruce SW is a stump with lower blaze visible.

(I6) Recovered the 1971 monument in good condition. The 1971 witnesses were not found. The position of the Maple NBT is now occupied by a clump of small diameter Maple trees. The monument was found 39.781 chains south of corner I5 of record and I accept the monument as a careful and faithful reestablishment of the position of the original corner. The corner falls on the north edge of an E-W powerline clearing.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H7) Found 1"ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:  
 16" Cedar N10E 30.0' old blazes (1963 NBT)  
 5" B.Spruce N69E 31.5' mrkd "1/4S NBT"  
 6" B.Spruce S82W 27.3' do  
 7" B.Spruce N32W 22.0' do  
 Set sq'd post adjacent. Bearings magnetic.

(I6) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 13" Maple N17E 3.1' mrkd "1/4S NBT"  
 5" Sugar N35E 34.3' do  
 4" Sugar N60E 23.9' do  
 9" Sugar N64W 25.3' do  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 05/28/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

