

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____ T _____ R _____ T _____ R _____	_____
2. Property Controlling in Section	S 15 T 48N R 32W S 15 T 48N R 32W S _____ T _____ R _____	4 1 _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 4 03/20/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(4-Sec. 15) Northwest 1/16 corner, Section 15. Not established in the original survey.

(1-Sec. 15) West 1/16 corner between Sections 10 and 15. 1970 - A.O.Enger RLS monumented the corner midway and on line between corners 20.037 chains east and west. Set 1"IDx36" I.pipe with 4" alum. cap. Balsam 6" S59 1/2W 29.2', Balsam 4" N52W 18.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(4-Sec. 15) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

(1-Sec. 15) Recovered the 1970 monument at record bearing and distance from the 1970 witnesses. The monument was found to have been installed in an erroneous position, 47' west of the midway position intended in 1970. Established and monumented this date the proper corner position midway and on the Section line between Section corner 1321.61' west and Quarter corner (remonumented by the undersigned) 1321.61' east. The 1970 monument could not be extracted. Its alum. cap was broken off and the pipe was driven below the ground surface.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 6" Spruce S49W 11.6' mrkd "1/16S BT" 3" Spruce N03W 21.7' do 3" Spruce N16E 22.4' do 3" Spruce East 5.3' do Set sq'd post adjacent. Bearings magnetic.	(1) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 5" Balsam N02E 36.2' mrkd "1/16S BT" 9" Cherry S70E 28.1' do 9" Balsam S17W 39.1' do 5" Cherry N22W 21.5' do Sq'd post adjacent. Bearings magnetic.
--	---

Signed by

Stephan J. Szyszkoski

Date

05/28/2008

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources, Office of Land and Facilities

