

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 48N R 32W	15
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S T _____ R _____	_____
	S 15 T 48N R 32W	5
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 15 03/17/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I5) Corner common to Sections 10-11-14-15. 1970 - Reestablished by A.O.Enger RLS by double proportionate measurement to the original record between corners 1 mile north, east and west, and 2 miles south. Set 1"IDx48" iron pipe with 4" brass cap. B.Spruce 5" S64E 21.8', B.Spruce 9" S30W 32.8', B.Spruce 7" N82W 27.3'.

(5-Sec. 15) North 1/16 corner, Section 15. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I5) Recovered the 1970 monument in good condition and at record bearing and distance from the 1970 witnesses, all now rotting stumps with no markings visible. Accepted same as a careful and faithful reestablishment of the position of the original corner.

(5-Sec. 15) Established the corner midway and on a straight line between Quarter corner placed by the undersigned 1315.58' north and intersection of 1/4 lines 1315.58' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I5) Found 1"ID I.pipe with 4" brass MDNR cap. Set measuring nail with MDNR tag in the side of: 5" Tamarack N05E 33.1' mrkd "S11 NBT" 4" Tamarack N46E 18.8' do 8" Tamarack N87E 8.3' do 6" Tamarack S38E 11.6' "S14 NBT" Sq'd post adjacent. Bearings magnetic.	(5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 3" Sugar N22W 27.3' mrkd "1/16S BT" 11" Sugar S69E 8.0' do 15" Sugar S45W 23.4' do 11" Sugar N80W 10.0' do Sq'd post adjacent. Bearings magnetic.
--	--

Signed by *Stephan J. Szyszkoski*
 Surveyor's Michigan License No. 33986

Date 05/28/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

