

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 48N R 32W	J9
	T 48N R 32W	I8
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on J9 03/24/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J9) Quarter corner common to Sections 23-26. 1971 - A.O.Enger RLS found a squared wooden post on line and midway between Section corners. Mr. Enger accepted the position of the post and replaced it with a 1"IDx36" I.pipe with 4" aluminum cap. B.Spruce 6" S2E 14.6', Cedar 7" S36W 42.0'.

(I8) Quarter corner common to Sections 22-23. 1971 - A.O.Enger RLS reestablished the corner position midway and on the Section line between corners I7 and I9. Set 1"IDx36" I.pipe with 4" aluminum cap. Sugar Maple 6" S70W 14.1', Sugar Maple 6" S50E 14.4'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J9) Found the 1971 monument in good condition, verified the position with respect to section corners east and west, and accepted same as the best available evidence of the position of the original corner. The 1971 B.Spruce NBT was found in place at record bearing and distance, in good condition, with overgrown blazes.

(I8) Found the 1971 monument in good condition and at record bearing and distance from the remaining NBT Sugar SE, in good condition. Verified the position of the corner with respect to Section corners north and south and accepted the monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J9) Fd. 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of: 6" B.Spruce S01W 14.8' 1971 NBT 4" Cedar S58W 25.95' mrkd "1/4S NBT" 6 B.Spruce N35W 9.4' do 5" B.Spruce N61E 14.6' do Set sq'd cedar post adjacent. Bearings are magnetic.	(I8) Fd. 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of: 12" Sugar S46E 14.65' 1971 NBT 12" Maple S78W 16.95' mrkd "1/4S NBT" 8" Sugar N28W 14.0' do 7" Sugar N27E 17.8' do Set sq'd cedar post adjacent. Bearings are magnetic.
---	---

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/16/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division

16460
16461