

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>23</u> T <u>48N</u> R <u>32W</u>	<u>J8</u>
	S <u>23</u> T <u>48N</u> R <u>32W</u>	<u>9</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 9 05/20/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J8) Center of Section 23. Not established in the original survey.

(9-Sec. 23) East 1/16 corner, Section 23. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J8) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

(9-Sec. 23) Established the corner midway and on a straight line between Quarter corner 1327.47' east and Center of Section 1327.47' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 9" Sugar N46E 21.65' mrkd "C1/4 BT"
 4" Sugar S44E 10.35' do
 7" Sugar S88W 9.8' do
 4" Sugar N40W 23.3' do
 Sq'd cedar post adjacent. Bearings magnetic.

(9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 11" Cedar N26E 19.05' mrkd "1/16S BT"
 7" Cedar N86E 21.6' do
 6" Cedar S50E 6.9' do
 8" Cedar S71W 3.95' do
 Sq'd cedar post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/16/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division