

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 32W	K9
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T 23 R 48N R 32W	13
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 13 05/20/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K9) Corner common to Sections 23-24-25-26. 1960 - Remonumented by Neal Sperhake, RLS 7876, in the original position as determined from original B.T. Yellow Birch 18 N33E 11 links. Set 1"IDx36" galvanized iron pipe with aluminum Kimberly-Clark Corp. cap. Maple 9" N64W 39 links, Y.Birch 8" N72E 50 links, Maple 4" S42E 31 links, Y.Birch 7" S60W 54 links. Corner recorded in L2, P91, Baraga County Land Corner Records.

(13-Sec. 23) Southeast 1/16 corner, Section 23. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K9) Found the 1960 monument in good condition and at record bearing and distance from two remaining NBTs - the Maples SE and NW are in good condition with overgrown blazes. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

(13-Sec. 23) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. The 1/16 corner to the east (corner #14) is that established by the undersigned May 24, 2010 and not that monumented by A.O.Enger in 1971. The position for the corner falls in a timber cutting.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K9) Fd. 1"ID I.pipe with 4" alum. Kimberly-Clark cap. Set measuring nail with MDNR tag in:
 12" Maple N61W 25.65' 1960 NBT
 8" Maple S38E 20.65' do
 7" Sugar N61E 24.45' mrkd "S24 NBT"
 12" Sugar S48W 16.35' "S26 NBT"
 Sq'd cedar post adjacent. Bearings magnetic.

(13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 12" Maple N57E 49.1' mrkd "1/16S BT"
 8" Cherry S40E 10.7' do
 6" Cherry S45W 24.85' do
 11" Cedar N57W 55.45' do
 Sq'd cedar post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/16/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division